KADUR DIVISION.

ADVERTISEMENT.

The 29th April 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 28th May 1888, for restoring the Hosahalli Medikere, Registered No. 902, Tarikere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. and 3 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Hosahalli Medikere, Registered No. 902, Tarikere Taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract Estimate of restoring Hosahalli Medikere, Registered No. 902, Tarikere Taluk.

Items of Work.	Per.	Quantity.	Rate.	Cost.
Bund—				
Earthwork including watering and tamping ..	C. Yd.	14,003		
Rough stone work (new)	do	2,715		
Old rough stone work	do	50		
Turfing only front slope	S. Yd.	704		
Grade stones at every 1½ chain or 100 feet ..	No.	13		
Bench Mark stones	do	2		
Kodi—				
Excavation soft rock	C. Yd.	44		
Brick in surki mortar	C. Ft.	1,217		
Burnt stone slabs	S. Ft.	160		
Plastering with surki mortar	Sq.	3·20		
Sluice—				
Excavation, ordinary soil	C. Yd.	67		
Brick in surki mortar	C. Ft.	1,093		
Burnt stone slabs	S. Ft.	493		
Plastering with surki mortar	Sq.	5·06		

D. SITARAM RAO,
Executive Engineer.

PALACE DIVISION.

NOTIFICATION.

The 5th May 1888.

The right of grazing on the Bangalore Water-Supply Catchment grounds divided into lots as under will be sold by public auction by the Amildar of Bangalore at the Taluk Cutcherry, on Monday the 21st May 1888, between 11 A. M. and 5 P. M.

Lot	No. II	Area	240	acres.
Do	No. III.	do	194	do
Do	No. IV.	do	295	do
Do	No. V.	do	525	do

2. The terms of sale and other particulars may be obtained on application to the Amildar of Bangalore.

R. F. SCALDWELL,
Executive Engineer.